

Scope of Work

Objective:

- To install T-post and wind/snow erosion fence material near fields on NAPI property. T- post will be installed 10' apart and to the depth of 2' per post to support the erosion fence that is 4'x50' per roll. The estimated distance of fence material is 2 miles that will be installed with a technique to divert wind in another direction.

Description:

- The installation of the fencing material will take place in Block 8 and Block 9; 10 miles South of NAPI Region 2 scale and/or 10 miles south on 371 from NAPI main headquarters.
- The T-post and wind/snow erosion fence material will be installed near fields to divert wind and reduce erosion that could affect the growth of crop in the spring season.
- Site location will be flagged by NAPI.

Work scope Schedule/Duration:

- Work on the fencing will take place from 8am to 5pm; Monday to Friday.
- Workers/ Contractor will need to check in with NAPI Conservation Supervisor or Conservation Manager.
- Duration of the work being done should not proceed more than 2 weeks.
- Contractor to supply manpower, tools and all equipment to complete the job.

Contractor Requirements:

- Drivers must have a valid drivers license and appropriate vehicle documentation.
- Appropriate insurance is mandatory – *i.e. Liability Insurance and Workers Compensation.*
- NAPI Safety Contractor Checklist.
- W- 9 Form(s)
- Bid Bond is also recommended.

Report:

- A weekly log of events will be required by the contractor.
- Dated and documented events will be submitted to the Conservation Supervisor or Conservation Manager in a timely manner.
- Keeping in contact with the Conservation Supervisor or Conservation Manager is required.

Estimated Budget:

- \$50,000.00
- Budget includes wind fence material and Contractor that is selected.